

Project #25002 - Dillon Pines Townhomes: Paving and Drainage Improvements

Prepared By: CP

BID TAB Item	Description	BID TAB Quantity	Units	Unit Price	Total Price
General					
1	Mobilization	1	LS		\$ -
Demolition					
2	Demolish and Dispose of Asphalt Parking Lot	18493	SF		\$ -
3	Demolish existing concrete retaining wall. (Units 7S-12S)	1	LS		\$ -
4	Demolish existing wood wall along La Bonte	1	LS		\$ -
5	Traffic Control	1	LS		\$ -
Site Work					
6	Remove Trees	2	EA		\$ -
7	Relocate Shed	1	LS		\$ -
Paving and Grading					
8	Excavation	439	CY		\$ -
9	Export	425	CY		\$ -
10	Fine Grading	22,511	SF		\$ -
11	Subgrade Preparation & Compaction	19,862	SF		\$ -
12	Furnish & Install 4" Asphalt Paving	483	TON		\$ -
13	Furnish & Install 6" Class 6 Aggregate Base Course	662	TON		\$ -
14	Furnish and Install Boulder Retaining Wall	369	FF		\$ -
15	Furnish and Install 2' Wide Curb and Gutter	84	LF		\$ -
16	Furnish and Install 4' Wide Valley Drain Pan	257	LF		\$ -
17	Topsoil & Seed	2,649	SF		\$ -
18	Erosion Control	1	LS		\$ -
19	Furnish and install sidewalk on La Bonte	240	SF		\$ -
20	Furnish and install sidewalk at units 1N and 2N	280	SF		\$ -
21	Furnish and install 6" concrete shed pad	80	SF		\$ -
22	Furnish and install parking lot striping	1	LS		\$ -
Utilities					
23	Furnish and Install 6" SDR-26 PVC Sewer Pipe	110	LF		\$ -
24	Furnish and Install 48" manhole complete	1	EA		\$ -
25	Furnish and Install 6" PVC Cleanouts	3	EA		\$ -
26	Furnish and Install 6" PVC to 4" cast iron adapter	1	EA		\$ -
27	Remove and Dispose of Existing Fire Hydrant. Remove and Dispose of Asphalt to Centerline of Street. Remove and dispose of sidewalk.	1	LS		\$ -
28	New Fire Hydrant (FOB) Materials Only	1	LS		\$ -
29	Install New Fire Hydrant Assembly. Patch Street to Centerline of Road	1	LS		\$ -
30	TV Inspection of sewer	1	LS		\$ -
31	Furnish and install striping along La Bonte	20	LF		\$ -

Bid Total: \$ -

